TUMKUR DIVISION.

Notification dated 22nd February 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 8th March 1937, for restoring breached Kuradihalli minor tank, Register No. 23, Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 5th March 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring breached Kuradihalli minor tank, Kunigal Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, and also deposit another Rs. 450 in default of which his tender will be considered cancelled and his earnest money already deposited will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per current schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. A reserve of 10 per cent on work done will be withheld in bills and will be paid back in the final bill.

Abstract estimate for restoring breached Kuradihalli Minor Tank, Registered No. 23 of Kunigal Taluk, Tumkur District.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund R. L. 55·00.		Rs. a. p.		
1	Cutting jungle and removing anthills ..	Each grade.	2 0 0	16	
2	Cutting trenches on the old bund $\frac{1}{2}' \times \frac{1}{2}'$ ..	Yds.	0 0 1	2,000	
3	Cutting trenches in toe of bund $3' \times \frac{3}{4}'$ ..	,,	0 0 3	500	
4	Earthwork to bund with watering and tamping including carting (with $\frac{1}{4}$ gravel)	C.yd.	0 4 6	6,135	
5	New rough stone revetment with jelly wedging	,,	1 12 0	651	
6	Old stone revetment with jelly wedging ..	,,	0 12 0	1,809	
7	Gravel backing behind revetment ($\frac{1}{3}$ of revetment quantity)	,,	0 8 0	820	
8	Turfing including watering	Syd.	0 0 9	5,2	
9	Providing and fixing new grade stones with chiselling figures and painting	Each	2 8 0	7	
10	Refixing the old grade stones and painting, etc.	..	1 0 0	10	
11	New Index stone with painting	..	1 0 0	17	
12	Register No. stone	..	5 0 0	1	
13	B. M. Stones	..	3 0 0	2	
14	Gauge stone	..	15 0 0	1	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	Breach Filling.				
1	Clearing sand	C.yd.	0 2 6	770	
2	Clearing silt	,,	0 3 6	578	
3	Earthwork (⅓ gravel and ⅔ good soil) ..	,,	0 8 0	4,739	
4	Puddle wall	..	0 10 0	557	
	Waste Weir R. L. 50·00.				
1	Earthwork excavation and using to bund ..	C.yd.	0 4 0	296	
2	Granite jelly concrete in surki mortar ..	C.ft.	0 4 0	260	
3	Burnt stone slabs 6" thick, dressed and fixed ..	S.ft.	0 6 0	308	
4	Fixing iron joggle with molten lead	Each	0 12 0	12	
5	Burnt brick in surki mortar	C.ft.	0 4 6	427	
6	Plastering with surki mortar	Sqr.	3 12 0	10·35	
7	Rough stone work	C.yd.	1 12 0	61	

D. KRISHNA RAO,
Executive Engineer.

WATER SUPPLY DIVISION, BANGALORE.

Abstract Notification dated 24th February 1936.

The attention of the public is hereby invited to the detailed notification, dated the 10th February 1937, published on page 224 of the *Mysore Gazette, dated* the 18th February 1937, regarding auctioning of empty alum bags at Thippagondanahalli on 1st March 1937.

V. GANESHA IYER,
Executive Engineer.

NANDI HILL STATION.

(Managed by the Government of Mysore.)

Nandi Hill Station (4851 feet), 35 miles from Bangalore, has a salubrious climate. The temperature on the hottest summer day is about 80° and on the average it is ten degrees cooler during nights than that of the surrounding plains. The fortress is of historic interest. There are train and motor bus services. The motorable road to the top of the Hill is nearing completion. During the season railway concession tickets are available. A Government Dispensary and an Ayurvedic Vaidyasala are kept up. There is a telegraphic and telephone connection from Nandi Railway Station to the top of the Hill. The Bungalows have fine rooms provided with furniture and electric lights and are suitable for all classes of people. Water tap connections have been given to all the buildings. There are both European and Indian Hotels. Facilities for outdoor and indoor games are provided. Post Office and Police Station are opened during the season.

The scenery is picturesque with beautiful gardens and shady walks. Further particulars may be obtained from the undersigned.

M. NARAYANA REDDY,
Qffg. *Superintendent,*
Hill Stations in Mysore.

LAL-BAGH,
BANGALORE.

Printed by the Superintendent at the Government Press, Bangalore—1937